

# New York State DEC

## *Draft Supplemental Generic Environmental Impact Statement on the Oil, Gas and Solution Mining Regulatory Program*

<http://www.dec.ny.gov/energy/58440.html>

*NTC Consultants (NTC) estimated required truck trips per well for the noted phases requiring transportation as follows:*

### **Drilling Rig Mobilization, Site Preparation and Demobilization**

- Drill Pad and Road Construction Equipment 10 – 45 Truckloads
- Drilling Rig 30 Truckloads
- Drilling Fluid and Materials 25 – 50 Truckloads
- Drilling Equipment (casing, drill pipe, etc.) 25 – 50 Truckloads
- Completion Rig Mobilization and Demobilization
- Completion Rig 15 Truckloads

### **Well Completion**

- Completion Fluid and Materials 10 - 20 Truckloads
- Completion Equipment (pipe, wellhead) 5 Truckloads
- Hydraulic Fracture Equipment (pump trucks, tanks) 150 - 200 Truckloads
- Hydraulic Fracture Water 400 - 600 Tanker Trucks
- Hydraulic Fracture Sand 20 - 25 Trucks
- Flow Back Water Removal 200 - 300 Truckloads
- Well Production
- Production Equipment 5 – 10 Truckloads